


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Kingman County. Sec. 13 Twp. 28S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Braden Drilling, Inc.  
Lease Name McPheeters Well No. 1  
Office Address 1620 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 29, 19 68  
Application for plugging filed 19 68  
Application for plugging approved November 29, 19 68  
Plugging commenced November 29, 19 68  
Plugging completed November 29, 19 68  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19 68  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Ralph Warren)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4395 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	276'	8-5/8"	11/21/68	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud from Total Depth to 250 Feet;  
1/2 sax Hulls, Plug and 25 sax Cement;  
Mud to 40 Feet; 1/2 sax Hulls & Plug  
bridged with Kelly and 10 sax Cement  
to Base of Cellar; 2 sax Cement in  
Rat Hole. Job Completed @ 4:15 P.M.  
on 11/29/68.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Sage Drilling Co. (If additional description is necessary, use BACK of this sheet)  
Address 500 Bitting Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
T. M. McCaul, Jr. of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.


(Signature) T. M. McCaul, Jr.

500 Bitting Building, Wichita, Kansas  
(Address)

Subscribed and Sworn to before me this 2nd day of December 19 68

My commission expires November 26, 1970.

Louise K. Whitted - Notary Public.



15-095-201260000

DRILLERS LOG

McPHEETERS NO. 1

SURFACE CASING:	OPERATOR: Braden Drilling, Inc.	DESCRIPTION:
8-5/8" @ 276' w/200 sax Cement	CONTRACTOR: Sage Drilling Co.	C NE SW Sec. 13-28S-8W Kingman Co., Kansas
TOTAL DEPTH: 4395'	COMMENCED: November 21, 1968	ELEVATION: 1581KB
	COMPLETED: November 29, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	38	
Red Bed	38	278	
Red Bed, Shale & Shells	278	820	
Shale	820	1425	
Shale & Lime	1425	1715	
Lime & Shale	1715	2001	
Shale & Lime	2001	2405	
Lime & Shale	2405	2895	
Lime & Shale w/Sand Streaks	2895	3180	
Lime & Shale	3180	3355	
Lime	3355	3450	
Cherty Lime & Shale	3450	3517	
Lime, Shale & Chert	3517	3615	
Lime	3615	3725	
Lime & Shale	3725	3790	
Lime & Chert	3790	4129	
Lime, Chert & Shale	4129	4210	
Lime & Shale	4210	4353	
Shale	4353	4380	
Chert & Lime	4380	4395	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. M. McCaul, Jr.  
T. M. McCaul, Jr.

Subscribed and sworn to before me this 2nd day of December, 1968.



Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1970.