

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 17 TWP. 28S RGE. 10W E/W
Location as in quarters or footage from lines:
SE SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Mull Drilling Company, Inc.
Lease Name Willinger Well No. A #1
Office Address Main 221 Suite 300 Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 7-22-81
Plugging completed 8-6-81
Reason for abandonment of well or producing formation _____

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett
Maurice V. Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4240'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	283'	none
				5-1/2"	4239'	2905'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in on location. Ran sand to 4090' and set 5 sacks cement. Got 23" stretch. Shot and worked pipe @3302', 3206', 3107', 3009', and 2913'. Layed down 87 joints. Plugged well with 15 sacks gel, 8 sacks hulls, 10 sacks gel, and 125 sacks 50/50 pos 4% gel3%CC. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF KANSAS COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 1981

My Commission expires:



Joan Kelso
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1981
8-12-81
CONSERVATION DIVISION
Wichita, Kansas