

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 23 Twp. 28 Rge. (E) 10 (W)

Location as "NE/CNW&SW&W" or footage from lines NW NW NW

Lease Owner Barbara Oil Company

Lease Name Dbane Well No. 1

Office Address 322 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed Sept. 22, 19 56

Application for plugging filed Verbally Sept. 22, 19 56

Application for plugging approved " Sept. 22, 1956 19

Plugging commenced Sept. 22, 1956 19

Plugging completed Sept. 22, 1956 19

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes verbally

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4581 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to within 250' of the top, set plug - 20 sacks cement, mud to within 40' of top, set plug, 10 sacks cement to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address Beacon Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. R.F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] Landman
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 56

[Signature] Notary Public.

My commission expires March 2, 1957

STATE OF KANSAS
SEP 26 1956 9-26-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 23, T. 28, R. 10W
BOOK PAGE 102 LINE 5

BARBARA OIL COMPANY
 #1 Doane
 NW NW NW Sec. 23-285-10W
 Kingman County, Kansas

Drilled By: Beardmore Drilling Company
 Drilling Commenced: 9-8-56
 Drilling Completed: 9-22-56

Casing:
 254' of 8-5/8" set @ 252' with 200 sacks cement on 9-8-56.
 Cement circulated.

Elevation:
 KB 1695

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand	100
Shale and Shells	252
Shale and Shells	1380
Lime and Shale	1450
Lime	1935
Lime and Shale	2080
Lime and Shale	2810
Lime and Shale	3125
Sand	3535
Lime	3680
Lime	3825
Lime	3935
Lime and Shale	4050
Lime and Shale	4114
Chert	4130
Chert	4145
Lime and Chert	4180
Lime and Shale	4230
Lime and Shale	4400
Lime	4415
Lime	4450
Lime and Shale	4478
Sand and Shale	4540
Lime	4582
Rotary Total Depth	4582

TOPS

Heebner	3372
Douglas	3495
Kansas City	3570
Mississippi	4114
Viola	4396
Simpson	4477
Arbuckle	4557

DRILL STEM TEST #1 - 4110-4145 Shut in 20 min., open 1 hr., shut in 20 min.
 Recovered 35' muddy water. BHP 1080, IF 50, FF 60.

DRILL STEM TEST #2 - 4397-4400 Open 30 min., shut in 20 min. Recovered
 30' oil and gas cut mud, some free oil in tool.
 BHP 365, IF 15, FF 15.

DRILL STEM TEST #3 - 4397-4401 Shut in 30 min., open 2 hrs., shut in
 45 min. Recovered 10' oil cut mud, 35' oily water.
 IBHP 1605, FBHP 1610, IF 15, FF 15.

STATE OF KANSAS)
) ss
 COUNTY OF SELWICK)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 4 1956

CONSERVATION DIVISION

I, the undersigned, being duly sworn on oath state that the above and
 within statement is a true and correct record and log of the well drilled
 on the location above-described, to the best of my knowledge and belief.

PLUGGING
 FILE SEC. 23 T. 28 R. 10W
 BOOK PAGE 102 LINE 5

My commission expires Jan. 28, 1960

Heber Beardmore
 Heber Beardmore

Subscribed and sworn to before me this 28th day of September, 1956.

Leonard P. Tolle