


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 23 Twp. 28-S Rge. 10-W (EX 10) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines. NE NE NE
Lease Owner Barbara Oil Company
Lease Name Doane Well No. 2
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed December 19, 19 56
Application for plugging filed December 19, 19 56
Application for plugging approved Orally December 19, 19 56
Plugging commenced December 19, 19 56
Plugging completed December 19, 19 56
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.M. Brundage, Hoisington, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4581 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to within 240' of the top, set bridge plug with hulls on top heavy mud to 35' - plug and 10 sacks cement. 20 sacks cement on top of plug at 240'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Co.
Address Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
L.W. Davidson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.W. Davidson
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1956

Mildred Fisher
Notary Public.

My commission expires March 2, 1957

PLUGGING
FILE SEC. 23 T. 28 R. 10.W
BOOK PAGE 127 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
12-20-56

ROTARY DRILLING LOG

OPERATOR: Barbara Oil Company
Doane No. 2
NE NE NE Sec. 23-28S-10W,
Kingman County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 12/1/56
COMP: 12/19/56

Remarks: Set 8-5/8" surface casing
at 257' cemented with 200 sacks Pozmix
2% C.C.

Formations:


Sand	112'
Shale & Red Bed	257'
Sand & Shale	425'
Red Bed Shale & Shells	835'
Anhydrite & Shale	881'
Shale & Shells	1060'
Shale, Shells & Salt	1115'
Lime & Shale	1530'
Lime	1705'
Lime & Shale	1770'
Lime & Shale Sdy Stks.	1910'
Lime	2025'
Lime & Shale	2640'
Lime	2725'
Lime & Shale	3270'
Lime	3345'
Lime & Shale	3435'
Shale Lime & Sand	3460'
Sand & Shale	3520'
Lime & Shale	3595'
Lime	4100'
Chert	4115'
Chat	4154'
Lime & Shale	4195'
Lime & Dolomite	4210'
Shale & Lime	4245'
Shale	4350'
Shale & Lime	4392'
Lime	4420'
Lime & Shale	4445'
Lime	4455'
Shale	4466'
Shale & Sand	4510'
Shale Lime & Sand	4552'
Lime	4580'
Rotary Total Depth(D&A)	4580'

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R.R. McNicol

R. R. McNicol



RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1956
CONSERVATION DIVISION
Wichita, Kansas