

15095-2113-0000

Give All Information Completely
Make Required Affidavit - Mail
Or Deliver Report To:

Conversation Division
State Corporation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

Kingman County, Sec. 12 S Twp. 28 Rge. 7W E
Location As "NE/CNW 1/4 SW1/4" Or Footage From Lines
C NW SW

Lease Owner Perto-Dynamics Ltd.

Lease Name Closson Well No. #1

Office Address Bldg. 1, Suite 207
555 North Woodlawn, Wichita, Ks.

Character Of Well (Completed As Oil, Gas Or Dry Hole)
Dry Hole

Date Well Completed 7-15 19 81

Application For Plugging Filed 7-15 19 81

Application For Plugging Approved 7-15 19 81

Plugging Commenced 7-15 19 81

Plugging Completed 7-15 19 81

Reason For Abandonment Of Well Or Producing Formation

Dry Hole

If A Producing Well Is Abandoned, Date Of Last Producti

19

Was Permission Obtained From The Conservation Division
Its Agents Before Plugging Was Commenced? Yes

Name Of Conservation Agent Who Supervised Plugging Of This Well

Producing Formation Depth To Top Bottom Total Depth Of Well 4325'

Show Depth And Thickness Of All Water, Oil And Gas Formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	4325'	None

Describe In Detail The Manner In Which The Well Was Plugged, Indicating Where The Mud Fluid Was
Placed And The Method Or Methods Used In Introducing It Into The Hole. If Cement Or Other Plug
Were Used, State The Character Of Same And Depth Placed, From Feet To Feet
For Each Plug Set. 1st @ 300' w/60 sx 50-50 Poz 3% cc

2nd @ 40' w/10 sx

15 sx in rat hole

Please Note: (If Additional Description If Necessary, Use Back Of This Sheet)

Name Of Plugging Contractor Ramco Drilling Co.

State Of Kansas County Of Sedgwick ss: J. V. Crawford

of Ramco Drilling Company

being first duly sworn on oath, says: That I have knowledge of the facts, statements and
matters herein contained and the log of the above described well as filed and that same are tru
and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1981
CONSERVATION DIVISION
Wichita, Kansas

THE RAMCO DRILLING CORPORATION

Signature: J. V. Crawford

(Address)

Subscribed And Sworn To Before Me This August Day Of August, 19 81

JUANITA L. BOTKIN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 6-30-83

Juanita L. Botkin
Notary Public

My Commission Expires:

W E L L L O G

15-095-21113-0000

WELL NAME: Closson #1

OPERATOR: Petro Dynamics Ltd.

SPUD DATE: 7-1-81

CONTRACTOR: Ramco Drilling Co.

COMPLETION DATE: 7-15-81

CASING: 24# 8 5/8" w/125 sx cmn,
2% cc, 3% gel

LOCATION: C NW SW 12-28S-7W

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Soils	0	40
Red Bed and Shale	40	259
Shale and Red Bed	259	300
Shale and Shells	300	950
Red Bed and Shale	950	1015
Anhydrite	1015	1042
Shale and Lime	1042	1400
Lime	1400	1412
Shale and Lime	1412	2255
Lime and Shale	2255	2468
Shale and Lime	2468	2690
Toronto (Lime)	2690	2890
Shale and Lime	2890	3134
Lime and Shale	3134	3340
Shale and Lime	3340	3483
Lime and Shale	3483	3865
Mississippi	3865	3966
Lime and Shale	3966	4083
Shale	4083	4177
Shale and Lime	4177	4260
Viola	4260	4276
Lime	4276	4325
RTD	4325	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 13 1981
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

By: [Signature]

Subscribed and sworn to before me on this 11th day of August, 1981.

[Signature]
 Notary Public



My Appointment Expires: