


15-095-20599-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 15 Twp. 28 Rge. 7W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
Lease Owner C NW/4
Lease Name Mack Oil Co. Well No.
Rich #1
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8/18/80 19
Plugging completed 8/25/80 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
depleted. 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of well 4432
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				805/8	279	none
				4 1/2"	4134	3260'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Squeezed 4 1/2 casing with 1 sack hulls, 35 sacks cement, pumped plug to 3600'. Shot pipe at
3320', 3245', pulled 82 joints. Squeezed hole with 15 sacks gel, 8 sacks hulls, 10 sacks
gel. Released plug and displaced with 125 sacks 50-50 pozmix, 4% gel and 3% ee.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1980
Conservation Division
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed, and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 80

Margaret Melcher
Notary Public.

My commission expires



DRILLER'S LOG

15-095-20599-0000

COMPANY: Mack Oil Co.

SEC. 15 T. 28S R. 7W

WELL NAME: Rich #1

LOC. C NW/4

COUNTY: Kingman

RIG NO. #7

TOTAL DEPTH 4430'

ELEVATION

COMMENCED: 6-24-77

COMPLETED: 7-7-77

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 279' w/200 sx., 2% gel, 3% cc.

PRODUCTION: 4 1/2" @ 4133.96' w/25 sx. 50/50 poz., 10% salt, 3/4 of 1% CFR2, and 125 sx. common. 18% salt, 1% CFR2.

LOG

(Figures Indicate Bottom of Formations)

Sand	281
Shale	1512
Shale & Lime	1780
Shale	2765
Shale & Lime	3340
Lime	3450
Shale & Lime	3850
Lime	4430
<u>ROTARY TOTAL DEPTH</u>	<u>4430</u>

RECEIVED
STATE CORPORATION COMMISSION
JUL - 7 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Rich #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 11 day of July, 1977.

My Appointment Expires:

10-4-79

Juanita M. Green
Juanita M. Green

