

WELL LOG
Sinclair Oil & Gas Co

R.T. Burcher # 1
NE/4, 9-24S-19W, Edwards Co., Kas
330' fm Sth & East lines
Elevation 2162
Location by Son Construction Co.-
R.A. Halfast, Engr. 9/8/1950

R.W. Rine Drlg Co., Rotary
Began drlg 9/18/50 3:00AM
Comp. drlg 10/8/50
T.D. 4997' in Arb.
Dry hole

Drillers Log

Corrected to Surface Level
Add 2 1/2' for derrick flr meas.
Add 5' for Kelly Bushing Meas.

Clay-Sand-Gravel	215'
Shale	395
Red Bed	613
Set 10-3/4" csg @ 264' w/150 sx	
Red Bed-Shells-Shale	1125
Shale-Shells	1270
Anhydrite	1300
Shale & Lime Shells	1490
Shale-Shells	1895
Shale-Lime	2215
Lime-Shale	2355
Lime	2545
Lime-Shale-Sand	2640
Lime-Shale	2905
Shale-Lime	3285
Lime	3400
Lime-Shale	3460
Lime	3640
Lime-Shale	3683
Lime	3905
Shale	3986
Lime	4160
Lime-hard	4177
Lime-soft	4187
Lime-hard	4203
Lime	4361
Shale-Lime	4433
Lime-Shale	4513
Shale	4531
Shale-Lime	4540
Lime	4550
Lime & Chert	4580
Lime	4628
Lime-Shale	4665
Lime-Chert	4720
Lime-Shale-Chert	4784
Lime	4935
Shale-Lime	4970
Lime	4997

Sample Tops

Topeka	3485'	no show
Heebner Shale	3857-3863	
Lansing	3960'	no show
good porosity	4177-4187'	no show
Conglomerate	4492	
Mississippi	4533	
Chert	4533-4584'	
Misener	4618-4663'	
Mississippi	4618	
D.S.T.	4538-4550'	tool open
1 hr	210'	water
Initial flo press.	150#	
Final flo press.	200#	
BHP	1050#	
Viola	4663'	
Simpson	4921'	
Arbuckle	4965'	

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1950
CONSTRUCTION
Wichita, MO

PLUGGING
FLR SEC 9 T 24 R 19 W
PAGE 34 LINE 15

Ran Schlumberger 10/8/1950
No show of Oil or Gas in any formation
Completed testing 10-9-1950
Completed plugging hole 10-9-1950