

4-8-92
50ft + down to top of cement

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20, 403-0000

LEASE NAME DECKERT

WELL NUMBER 1-5

440 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 5 TWP. 24 RGE. 17 (N or W)

COUNTY EDWARDS

Date Well Completed _____

Plugging Commenced 4-2-92

Plugging Completed 4-6-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. HOLL CO.

ADDRESS 6427 EAST KELLOGG P.O. Box 780167
WICHITA, KS. 67278-0167
PHONE (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-3-92 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation PERFS: 4354-58 Depth to Top _____

PBTP: Bottom 4415 T.D. 4463

Show depth and thickness of all water, oil and gas formations. ...

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	252	8 5/8	252	0
		0	4460	4 1/2	4460	1995 FT. - 44 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

DUMPED SAND + CEMENT TO 50 FT. ABOVE TOP PERFS. SHOT OFF CSA.
AT 1995 FT. + PULLED 44 JTS. OF CSA. PLUS CUT OFF JT.
4-6-92 - 9:00 A.M.: TOP HOLE PLUGGED WITH: 300# HULLS - 10 SX GEL - 50 SX.
CEMENT - 10SX GEL - 100# HULLS - 8 5/8 PLUG - 125 SX. CEMENT - 60-40002 - 6% GEL.

(If additional description is necessary, use BACK of this form.)

4-10-92: Dumped Redi-mix TO TOP.
Name of Plugging Contractor PRATT WELL SERVICE INC. License No. 5893

Address P.O. Box 847 PRATT, KS. 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. HOLL CO. RECEIVED 4-2-92

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY PLUGGING CONTRACTOR
(Employee of Operator) of (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO PWS, INC.



SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 92

Dorothy M. Ferguson
Notary Public

My Commission Expires February 6, 1993