


WELL PLUGGING RECORD

All Information Completely
Required Affidavit
File or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County, Sec. 6 Twp. 24 Rge. 16 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NW NW NE



Locate well correctly on above
Section Plat

Lease Owner Kansas Exploration Co. (Drillers-Producers)
Lease Name Mead Well No. #1
Office Address Box 368, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 1-22-63 19____
Application for plugging approved _____ 19____
Plugging commenced 1-29-63 19____
Plugging completed 2-4-63 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4393' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4240' - mixed and dumped 5 sacks cement thru dump bailor.
Mudded hole to 215' - sat 10' rock bridge, mixed and ran 5 sacks cement.
Squeezed hole with 15 sacks gel and 75 sacks cement by Sun Oilwell Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of February, 1963

My commission expires 24 October 1964
Ernest D. Miller Notary Public.

INVOICED

DATE 2/6/63
INV. NO. 6533-W

15-047-10048-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- KANSAS EXPLORATION CO.
Farm- Mead No. 1

SEC. 6 T. 24 R. 16W
NW NW NE

Total Depth. 4393'
Comm. 6-11-60 Comp. 6-24-60
Shot or Treated.
Contractor. Sierra Petroleum Co.
Issued. 12-3-60

County Edwards
KANSAS



CASING:
8 5/8" 228' cem w/175 sx.
5 1/2" 4316' cem w/75 sx.

Elevation. 2080' KB
Production. 59 BOPD

Figures Indicate Bottom of Formations.

sand	80
shale	360
sand	390
shale & red bed	565
sand	615
red bed	1067
Anhydrite	1098
shale & shells	1500
salt & shale	1615
shale & shells	1940
lime & shale	2385
lime	2425
lime & shale	3320
lime	3405
lime & shale	3809
lime	4235
lime, shale & chert	4257
chert	4270
Mississippi	4317
lime, shale & chert	4383
Viola	4393
Total Depth	
TOPS: SCOUT	
Anhydrite	1067
Heebner	3665
Brown Lime	3791
Lansing	3800
Base Kansas City	4080
Ft. Scott	4185
Cherokee Shale	4221
Mississippi	4247
Kinderhook Sand	4326
Viola	4366