

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 - 047-21,374-0000

LEASE NAME Mundhenke

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-21

3300 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 21 TWP. 24S RGE. 17W ~~18W~~ (W)

COUNTY Edwards

LEASE OPERATOR F. G. Holl Company

P. O. Box 780167

ADDRESS Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed 5-28-91

2:45 PM

Plugging Commenced 5-28-91

4:00 PM

Plugging Completed 5-28-91

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-28-91 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled?                      If not, is well log attached? Yes

Producing Formation                      Depth to Top                      Bottom                      T.D.                     

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	340'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet each set.

Filled hole with heavy mud. 50 sacks at 1170'; 40 sacks at 600'; 50 sacks at 360'; 15 sacks 60' to surface. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form. RECEIVED  
STATE CORPORATION COMMISSION  
MAY 31 1991

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129  
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

CONSERVATION DIVISION  
Wichita, Kansas

Richard L. Mead (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead

(Address) P. O. Box 129, Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 29th day of May, 1991



Agnes D. Wurst  
Notary Public = Agnes D. Wurst

My Commission Expires: 4-26-93

## STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MUNDHENKE #1-21

Located: C E/2 SW NW, Section 21-24S-17W, Edwards  
County, Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 21, 1991

COMPLETED: May 28, 1991

TOTAL DEPTH: 4750'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 8 joints 8 5/8", 23# new casing. 327.03' pipe set at 340' K.B. Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 2:00 PM, 5-21-91, by B. J. Titan.
90 - 342 Red Bed and Shale	
342 - 1765 Shale	
1765 - 4750 Lime and Shale	Plugged.

Deviation Survey: 1 1/4° at 4750'