

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,250-0000

LEASE NAME D. McKinney

WELL NUMBER "B" 1-13

SPOT LOCATION SW SW NE

SEC. 13 TWP. 24S RGE. 18 (W)

COUNTY Edwards

Date Well Completed 4-21-85
8:00 PM,

Plugging Commenced 4-21-85

Plugging Completed 10:20 PM,
4-21-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	309'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud plugged through open ended drill pipe. 50 sacks at 1190'; 50 sacks at 600'; 50 sacks at 320'; 1/2 sack hulls, plug and 10 sacks at 40'; 15 sacks in rathole. Used 60/40 Pozmix, 2% gel (4% total) and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

APR 25 1985
4-25-85
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary

(Address) P. O. Box 129, Sterling, Kansas



SUBSCRIBED AND SWORN TO before me this 22 day of April, 1985

[Signature]
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-89

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - D. McKINNEY "B" 1-13
 Located: SW SW NE, Section 13-24S-18W, Edwards County,
 Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 15, 1985

COMPLETED: April 21, 1985

TOTAL DEPTH: 4595'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 7 joints new 8 5/8", 23# casing. 296.27' pipe set at 309' K.B.
90 - 312 Shale	Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 6:00 PM, 4-15-85, by Howco.
312 - 1030 Shale, Sand, Red Beds	
1030 - 1180 Lime and Shale	
1180 - 1935 Anhydrite	
1935 - 4595 Lime and Shale	Plugged.

RECEIVED
 STATE CORPORATION COMMISSION

Deviation Surveys: 1° at 2152' APR 25 1985
 1° at 4432'
 CONSERVATION DIVISION
 Wichita, Kansas