

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 35 TWP. 24S RGE. 17W 18/W
Location as in quarters or footage from lines:
SW SW SE

Locate Well
correctly on above
Section Platt.

Lease Owner F. G. Holl
Lease Name Penka Well No. 2-35
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed September 27, 1983
Application for plugging filed September 27, 1983
Plugging commenced 9:00 AM September 27, 1983
Plugging completed 10:30 AM September 27, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 4380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	264'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud through open ended drill pipe, 50 sacks
at 1110'; 50 sacks at 420'; bridge, 1/2 sack hulls,
plug and 10 sacks at 40'. 15 sacks in rathole with
joint of drill pipe. Used 60/40 Pozmix plus 2% gel
(4% total) 3% cc. P

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) *F. A. Wuellner*
F. A. Wuellner, Secretary

(Address)
P. O. Box 129, Sterling, Kansas
67579

SUBSCRIBED AND SWORN TO before me this 28th day of September 19 83.



Agnes D. Wurst
Agnes D. Wurst, Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: 4-6-85

OCT 3 1983

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - PENKA #2-35

Located: SW SW SE, Section 35-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 21, 1983

COMPLETED: September 27, 1983

TOTAL DEPTH: 4380'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 70 Surface Soil and Sand	Ran 6 joints new 8 5/8", 24# casing.
70 - 267 Shale and Clay	251.99' pipe set at 264' K.B. Cemented with 210 sacks 60/40 Pozmix, plus 3% cc.
267 - 1109 Shale, Sand and Red Beds	Plug down at 4:00 PM, 9-21-83, by Howco.
1109 - 1127 Anhydrite	
1127 - 1160 Shale	
1160 - 2050 Shale, Lime Stringers	
2050 - 4380 Lime and Shale	Plugged.

Deviation Surveys: 1 3/4° at 2227'
1/2° at 4300'

RECEIVED
STATE CORPORATION COMMISSION

OCT 3 1983

CONSERVATION DIVISION
Wichita, Kansas