

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 12 TWP. 24S RGE. 18W E/W
 Location as in quarters or footage from lines:

Locate Well
 correctly on above
 Section Platt.

SW SW SE
 Lease Owner F.G. Holl
 Lease Name Wolfe Well No. 1-12
 Office Address 6427 East Kellogg Wichita, Kansas 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 7-16-81
 Plugging completed 8-7-81
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie
 Producing formation _____ Depth to top _____ bottom _____ T.D. ~~4695~~ 4575
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	257' 247'	none
				4-1/2"	444' 457'	288' 3055'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Moved in on location, ran sand to 4475' and dumped 4 sacks cement, pulled 18"
tension. Shot pipe @3825', 3610', 3415', 3230', & 3035'. Pulled 97 joints.
Squeezed hole with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and
displaced with 125 sacks 50/50 pos, 4% gel & 3% cc. Plugging completed.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 81

My Commission expires:



Joan Kelso
 RECEIVED Public.
 STATE CORPORATION COMMISSION

AUG 12 1981

CONSERVATION DIVISION
 Wichita, Kansas

WOLFE 1-12

SW SW 12-245-18W

15-047-20579-0000

Form 52-243



Logbook

Barbara Ray

Newton

FILE NO.

COMPANY F. G. HOLL

Hand Log
TOP Cement
3972

TOPS
AND DST
MARKED

WELL WOLFE # 1-12

FIELD

COUNTY EDWARDS

STATE KS

LOCATION:

STATE

Other Services

SW-SW-SE

APR 12 1979

COLC

SEC 12

TWP 24S

RGE 18W
CONSOLIDATED

CON

Permanent Datum

GL

Elev

Wichita, Kansas
2126

Elevation
2135

Log Measured from

KB

9

FT Above Permanent Datum

2132

Drilling Measured from

KB

2126

Date

10-5-79

Page 4506-10

Run No

ONE

Depth - Driller

4575

Depth - Logger

4572

Bottom Logged Interval

4572

Top Logged Interval

0

Casing - Driller

878 @ 247

Casing - Logger

4 1/2 @ 4571

15058 30-50 POS

Bit Size

7 7/8

Type Fluid in Hole

DRESSAC

Density and Viscosity

9.9 @ 58

pH and Fluid Loss

10.0 @ 13.2 cc

Source of Sample

FLOWLINE

Rm @ Meas. Temp.

.27 @ 74 °F

.17 @ °F

Rmf @ Meas. Temp.

.10 @ 74 °F

.13 @ °F

Rmc @ Meas. Temp.

.34 @ 74 °F

.30 @ °F

Source of Rmf and Rmc

CALC

CALC

Rm @ BHT

.17 @ 120 °F

@ °F

Time Since Circ.

2 hrs

Max Res. Temp. Deg F

120 °F

Equip No and Location

M-449 G.B

Recorded By

THABBARO

Witnessed By

PL. MOAR