

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,340-0000

LEASE NAME Wolfe

WELL NUMBER 3-12

1300' Ft. from S Section Line

2705' Ft. from E Section Line

SEC. 12 TWP. 24S RGE. 18 (EXX)(W)

COUNTY Edwards

Date Well Completed 6-5-89

1:30 PM

Plugging Commenced 6-5-89

3:30 PM

Plugging Completed 6-5-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl Company

P. O. Box 780167
ADDRESS Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-4-89 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D. 4575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Plugged with 50 sacks at 1200'; 50 sacks at 340';
10 sacks at 40' to surface. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, President
(Address) P. O. Box 129, Sterling, KS 67579

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1989
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1989

Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93



6-7-89

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - WOLFE #3-12

Located: C S/2, Section 12-24S-18W, Edwards County,
Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 30, 1989

COMPLETED: June 5, 1989

TOTAL DEPTH: 4575'

LOGCASING RECORD

0 - 60	Surface Soil and Sand	Ran 7 joints 8 5/8" casing. 297.19' set at 310' K.B. Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc.
60 - 312	Red Bed and Shale	Plug down at 12:30 PM, 5-30-89, by F. J. Titan.
312 - 1100	Shale and Red Beds	
1100 - 4575	Lime and Shale	Plugged.

Deviation Survey: 3/4° at 4420'

RECEIVED
STATE CORPORATION COMMISSION

JUN 7 1989

CONSERVATION DIVISION
Wichita, Kansas