

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21174-0000

LEASE NAME Wolf

WELL NUMBER 2-12-

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 24 RGE. 18 (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 8/17/89

Plugging Completed 8/22/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Hall

ADDRESS Box 158 Belpre, Kansas 67519

PHONE#(316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4551

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	253	none
				4 1/2	4507	2543

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3730, ran 4 sacks cement, shot pipe @ 3321', 2723', 2543'. Plugged with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls and 120 sacks 60/40 poz.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Hall

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 89

My Commission Expires:

IRENE HERZBERG
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp.

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - WOLFE #2-12

Located: NW NW SE, Section 12-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 17, 1984

COMPLETED: May 23, 1984

TOTAL DEPTH: 4549'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 95 Surface Soil and Sand	Ran 6 joints new 8 5/8", 23# casing.
95 - 256 Shale, Clay	241.45' pipe set at 253' K.B. Cemented with 210 sacks 60/40 Pozmix plus 3% cc. Plug down at 6:15 PM, 5-17-84, by Howco.
256 - 925 Shale, Sand, Red Bed	
925 - 1184 Shale	
1184 - 1204 Anhydrite	
1204 - 1434 Shale	
1434 - 4549 Lime and Shale	Ran 112 joints 4 1/2", 10.5# casing. 10 joints were used. 4543' pipe set at 4547' K.B. Cemented with 100 sacks Lite and 125 sacks F. G. Holl mix. Plug down at 6:15 PM, 5-23-84, by Howco.
	Plugged water well and rathole.

STATE OF KANSAS
 DEPARTMENT OF REVENUE
 COMMISSION

AUG 2 1989

CONSERVATION DIVISION
 Wichita, Kansas

Deviation Surveys: 1° at 1434'
 1° at 4440'