

15-047-20233-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 12 Twp. 24S Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE NW SW

Lease Owner Sterling Drilling Company, et al
Lease Name Taylor A-1 Well No. 1

Office Address P. O. Box 129, Sterling, Kansas 67579

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed May 9, 1977 19

Application for plugging filed May 9, 1977 19

Application for plugging approved May 9, 1977 19

Plugging commenced 4:00 PM, May 9, 1977 19

Plugging completed 6:30 PM, May 9, 1977 19

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Depth to top Bottom Total Depth of Well 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
35 sacks at 240'; heavy mud to 40';
Halliburton plug, 1/2 sack hulls;
10 sacks to surface; 3 sacks in rathole;
2 sacks in mousehole.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1977 5-12-77

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY


(Signature) *F. A. Wuellner*
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 77

CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - TAYLOR A-1

Located: SE NW SW, Section 12-24S-19W, Edwards County,
Kansas

OWNER: Kansas-Nebraska Natural Gas Company, Inc., Sterling Drilling
Company, et al

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 29, 1977

COMPLETED: May 9, 1977

TOTAL DEPTH: 4620'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 257 Sand and Shale	Ran 6 joints 8 5/8" casing, 242' set at 254' K.B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 1:15 PM, 4-29-77.
257 - 1242 Shale	
1242 - 1260 Anhydrite	
1260 - 2174 Shale	
2174 - 4050 Lime and Shale	
4050 - 4145 Lime	
4145 - 4430 Lime and Shale	
4430 - 4500 Lime and Chert	
4500 - 4600 Lime and Shale	
4600 - 4620 Lime	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1977

CONSERVATION DIVISION
Wichita, Kansas