

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Edwards SEC. 2 TWP. 24S RGE. 18W ~~RAW~~
Location as in quarters or footage from lines:
NE SW NE

Lease Owner F. G. Holl
Lease Name Sinden #1-2 Well No. 1-2
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed August 15, 1982
Application for plugging filed August 15, 1982
Plugging commenced 1:45 PM, August 15, 1982
Plugging completed 3:45 PM, August 15, 1982
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Carbutton

Producing formation _____ Depth to top _____ bottom T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	265'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged through drill pipe - 70 sacks at 780';
40 sacks at 210'; bridge of 1/2 sack hulls,
plug and 10 sacks at 40'. 10 sacks in rat
hole, with joint of drill pipe.
Used 50/50 Pozmix with 4% gel and 3% cc. - total 130 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Bernard Laudermilk (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) Bernard Laudermilk
Bernard Laudermilk, President
P. O. Box 129, Sterling, Ks 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 82.


My Commission expires: 4-6-85

Agnes D. Wurst
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1982

CONSERVATION DIVISION
Wichita, Kansas



STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

August 16, 1982

WELL LOG - - - - - SINDEN #1-2

Located: NE SW NE, Section 2-24S-18W, Edwards County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 9, 1982

COMPLETED: August 15, 1982

TOTAL DEPTH: 4600'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# new casing.
90 - 768 Shale	253.06' set at 265' K.B. Cemented
768 - 925 Shale and Sand	with 210 sacks 60/40 Pozmix with
925 - 1182 Shale and Shells	3% cc. Plug down at 11:30 AM, 8-9-82,
1182 - 1202 Anhydrite	by Howco.
1212 - 1735 Shale and Lime	
1735 - 2207 Shale and Lime Stringers	
2207 - 4600 Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1982

CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1 1/2° at 2207'
1/4° at 4472'