

15-155-02647-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

| | | | |
|--|---|--|--|
| | | | |
| | | | |
| | X | | |
| | | | |

Locate well correctly on above
Section Plat

RENO County. Sec. 26 Twp. 23S Rge. 4 (B) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. CNE SW
 Lease Owner Olson Drilling Company
 Lease Name J.H. Goering Well No "A" #1
 Office Address PO Box 2680 Tulsa 1 Oklahoma.
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed January 11th 1945
 Application for plugging filed December 11th 1944
 Application for plugging approved 8th 1944
 Plugging commenced January 6th 1945
 Plugging completed " 11th 1945
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Conservation Division

Name of Conservation Agent who supervised plugging of this well Mr. Durkee
 Producing formation Depth to top Bottom Total Depth of Well 3332 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|------|---------|--------|------------|
| Chat | Gas | 3292 | 3332 | 8-5/8" | 3242' | 1139.70 |
| | | | | 15 1/2" | 224' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled Hole with mud back to 220' run 30 Sks. cement.
 Mudded Hole back to 10' put in 10 Sacks cement to cellar base.

26 23 4W
 142 28

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Olson Drilling Company
 Address PO Box 2680 Tulsa 1 Oklahoma

STATE OF KANSAS, COUNTY OF RENO, ss.
 S. A. Keefover (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Keefover 1-15-45

Tr. 1. Burnton, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13th day of January, 1945

My commission expires June 19th 1948 Notary Public.

15-55-02647-0000

OLSON OIL COMPANY
J. H. GOERING #1
C NE SW 26 23S 4W
RENO COUNTY, KANSAS.

COMMENCED 3-15-32
COMPLETED 4-11-32
ELEVATION 1469'

CASING RECORD

0
214--Sand
224--Shale
450--Shale lime sh.
80--Broken lime
500--Lime
27--Broken lime
31--Shale
80--Lime
695-- Broken lime
710--Lime
730--Sand
810--Broken lime
16--Sandy shale
850--Lime
964--Broken lime
1035--Lime
50--Shale
1170--Broken lime
1200--Shale
1345--Broken lime
55--Sand
1400--Broken lime
18--Shale
.25--Broken lime
74--Lime
89--Brown shale
1510--Broken lime
1645--Shale & lime sh.
85--Broken lime
1720--Shale
1910-- " & lime sh.
85--Broken lime
2000--Shale & lime sh.
70--Broken lime
2157--Shale & lime sh.
2250--Lime
75--Shale & lime sh.
95--Lime
2323--Broken lime
67--Lime
2540--Shale & lime sh.
73--Sandy lime
2621--Broken lime
39--Shale&Lime sh.
57--Lime
97--Broken lime
2740--Lime
46--Shale
75--Shale & lime sh.
90-- " "

2867--Lime
3047--Broken lime
70--Shale & lime sh.
77--Broken lime
3195-- " " & Shale
3224--var. shale
29--Red rock
42--Chat & chert
92--Chat
3332--Chat
T₁D₂³

15 1/2" 70# 224'
8 5/8" 32# 3242'

26 23 4W
142 28

