

15-155-02656-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
808 Bittling Building  
Wichita, Kansas


OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Reno County. Sec. 26 Twp. 23S Rge. 4(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW SW  $\frac{1}{4}$   
Lease Owner Olson Drilling Co.  
Lease Name J.H. Goering A Well No. 9  
Office Address P.O. Drawer 2680, Tulsa 1, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 7 - 18 1937  
Application for plugging filed 12-13 1946  
Application for plugging approved 12 - 14 1946  
Plugging commenced 12 - 31 1946  
Plugging completed 1 - 13 1947  
Reason for abandonment of well or producing formation Oil exhausted



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production May 1944  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Hunton Lime Depth to top 3581 Bottom 3584 Total Depth of Well 3584 Feet  
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Hunton Lime	Oil	3581	3584	15 1/2"	255'	None
				9"	2831'	2667.15'
				5 3/16"	3579'	3059.61'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with mud from 3404 to 3315  
Ran 6 sacks of cement at 3315'  
Mud hole to 250'  
Set rock bridge at 250'  
Ran 30 sacks of cement at 250'  
Mud hole to 12'  
Ran 10 sacks of cement for cap in cellar

NOTE: This well was plugged back from the Hunton lime to the Chat, 3584 to 3404' on Sept. 23, 1946. The 5 3/16" casing was perforated with 112 shot from 3370' to 3315'. It was acidized with 2000 gal. of acid. No oil was found in this area.

FILE 26 23 4W  
BOOK 86 37

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to S.A. Keefover  
Address Burrton Kansas

STATE OF Kansas, COUNTY OF Harvey, SS. J. D. Mc Mannis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Mc Mannis  
Burrton Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of January, 1947

My commission expires 7/22/48  
Notary Public. 1-16-47

15-155-07656-0000

DLDG.  
OLSON ~~Oil~~ COMPANY  
J. H. GOERING "A" #9  
SW NW SW  $\frac{1}{4}$  26 23S 4W  
RENO COUNTY, KANSAS.

COMMENCED 4-28-37  
COMPLETED 7-18-37  
ELEVATION 1471'

CASING RECORD

Cement

15 1/2" 55# 255' W/ 225 Sax  
9" 40# 2831' W/ 45 sax  
5 3/16" 17# 3579' W/ 125 SAX

0  
20--Surface  
125--Sand  
50--Sandy shale & shells  
56--Sand  
255--Shale & shells  
340--Sandy shale & sh.  
785--Shale & shells  
849-- " lime  
926-- " broken lime  
68-- " Lime  
1038-- " broken lime  
1242-- " lime  
1312-- " broken lime  
60--Broken lime  
1600--Shale & shells  
67-- " broken lime  
1805-- " shells  
27--Lime  
1905--Broken lime  
45--Shale  
2089--Lime  
2132-- " shale  
63--Broken lime  
84--Lime  
2342-- " shale  
62--Shale  
95--Lime  
2491--Shale  
2525-- " & sand  
2663--Lime  
80-- " shale  
2703--Shale & sand  
30--Lime  
42--Broken lime  
2910--Lime  
14--Shale  
59--Lime  
92--Shale  
3027--Broken lime  
68--Shale & lime  
3167-- "  
97-- " " sh.  
3239-- " var.  
3441--Chat  
64--Lime  
98-- " , broken  
3581--Shale  
84--Lime  
T.D.

Plugging permit applied for 12/13/'46

FILE 26 23 44  
BOOK 86 37

STATE OF KANSAS  
COMMISSIONER  
JAN 18 1947