

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

*To be filed with State Corp. Comm*  
FORM CP-1  
15-047-21237-0000 Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-047-21,237<sup>0000</sup> (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl OPERATORS LICENSE NO. 5056  
ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207 PHONE # (316) 684-8481

LEASE (FARM) Adams WELL NO. 2-31 WELL LOCATION NE NW SE COUNTY Edwards  
SEC. 31 TWP. 24S RGE. 16 ~~(W)~~ TOTAL DEPTH 4515' PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A XX SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_  
SURFACE CASING SIZE 8 5/8" SET AT 309' CEMENTED WITH 225 SACKS  
CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Filled hole with heavy mud. Heavy mud  
plugged through open ended drill pipe - 50 sacks at 1110'; 70 sacks at 540'; bridge  
sack hulls and plug and 10 sacks at 40'; 15 sacks in rathole; 10 sacks in mousehole.  
Used 60/40 Pozmix, plus 2% gel, total of 4%, 3% cc.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10:00 PM, 12-10-84

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: \_\_\_\_\_

Jim Shriner PHONE # (316) 278-2131 **RECEIVED** DEC 17 1984  
STATE CORPORATION COMMISSION

ADDRESS P. O. Box 129, Sterling, Kansas 67579 CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142 12-17-1984  
P. O. Box 129

ADDRESS Sterling, Kansas 67579 PHONE # (316) 278-2131  
STERLING DRILLING COMPANY

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: F. A. Wuellner  
(Operator or Agent)

F. A. Wuellner, Secretary

DATE: December 11, 1984