

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. _____

LOCATION C 5W-5W-7W

SEC. 29 TWP. 24 RGE. 11 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Cooper

Operator C. R. A. Address Box 765 At Bend, Ks.

Field _____ County Stafford

Total Depth 3915 Feet.

Plugging Contractor Shamrock Drilling Co.

Plugging Contractor's License No. _____

Address 407 Rule Bldg. Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 321' c.w.c. 5 1/2" casing set
3897' w/ 75 sv cem. Sanded hole to 3890'
dump 5 sv cem. shot off and pulled 5 1/2"
Casing. Filled hole with heavy mud to
300' set rock bridge and dumped 20
sv cem. mud to 35' rock bridge and
10 sv cem. to base of cellar

7-27-55

Warren S. Garner
 District Conservation Agent

CONSERVATION DIV. Date July 25, 1955
 Wichita, Kansas

PLUGGING
 FILE SEC. 29 TWP. 24 R. 11 W
 BOOK PAGE 136 LINE 88