

1052391

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,944-0000  
C SW SE SEC. 25, T 24 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 600 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LEARNED WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 126.56

OPERATOR LICENSE # 30080

WELL TOTAL DEPTH 3894 FEET

OPERATOR: HONEY OIL CO., INC.

PRODUCTION CSG: SIZE 5 1/2" @ 3892' WITH 125 SX

NAME AND 8526 BOXTHORN

SURFACE CASING: SIZE 8 5/8" @ 253' WITH 200 SX

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 16 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3760-3780

SANDED TO 3590' AND DUMPED 5 SX CEMENT WITH A BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS -

10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG & 125 SX CEMENT.

MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 200 PSIG.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:54 PM DAY: 16 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

SANDED TO 3590' AND DUMPED 5 SX CEMENT WITH A BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS -

10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" PLUG & 125 SX CEMENT.

MAXIMUM PRESSURE 600 PSIG. SHUT IN PRESSURE 200 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY UNITED. RECOVERED 2610' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED  
5/25/00  
SIGNED  
61778  
WWW.NCL

Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

CONSERVATION DIVISION  
Wichita, Kansas

MAY 24 2000

RECEIVED  
STATE CORPORATION COMMISSION