

1 120897

3-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,677-0000
30' N of
SW NW SW, SEC. 16, T. 24 S, R. 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company

Name: P.O. Box 780167

Address: Wichita, KS 67278-0167

1680 feet from S section line

4950 feet from E section line

Lease Name Rudd "A" Well # 3-16

County Edwards

Well Total Depth 4485 145.76 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 1 p.m. Day: 4 Month: 3 Year: 19 94

Plugging proposal received from Art Merrick

(company name) F.G. Holl Company (phone) 316-995-3171

vers: 4 1/2" at 4472' w/225 sx cement, PBTD 4340', Perfs at 4367-71, 4289-93'

1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 4 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2383' of casing (S&P Dr.)
(if additional description is necessary, use BACK of this report)

observe this plugging.

INVOICED

DATE 3-14-94

INV. NO. 40098

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
MAY 19 1994