

1052319

STATE CORPORATION COMMISSION 5-18

API NUMBER 15-047-21,339-0000  
C N/2 SW SEC. 16, T 24 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3960 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME RUDD "A" WELL # 6-16

TECHNICIAN'S PLUGGING REPORT COUNTY EDWARDS

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 4410 143.33 FEET

OPERATOR: F.G. HOLL COMPANY LLC PRODUCTION CSG: SIZE 4 1/2" @ 4408' WITH 225 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 316' WITH 225 SX

ADDRESS WICHITA, KS 67278-0167

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 18 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4291-4301

1ST PLUG PUMPED 200# HULLS AND 25 SX COMMON CEMENT DISPLACED TO 3368' AT 1700 PSI.

SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 1118' WITH 10 SX GEL - 50 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:20 AM DAY: 18 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 200# HULLS AND 25 SX COMMON CEMENT DISPLACED TO 3368' AT 1700 PSI.

SPOTTED PLUGS THROUGH CASING.

2ND PLUG AT 1118' WITH 10 SX GEL - 50 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2428' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

DATE 6-3-99

INV. NO. 60999

JUN 03 1999 6-1-99