

8-9

To: 1 051339
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,624-0000
C SE _____, SEC. 17, T 24 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

1320 feet from S section line

1320 feet from E section line

Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67207

Lease Name Dutton Well # 2-17

County Edwards 143.00

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:37 a.m. Day: 9 Month: 8 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-995-3171

were: 4 1/2" at 4398' w/175 sx cement, PBTD 4360', Perfs at 4310-14, 4200-50'

1st plug pump 30 sx cement to 4200',

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 9 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to 4200',

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 350 psf and shut in 113 psi.

Witnessed by Steve Middleton.

8-14-90

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2438' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE: AUG 23 1990

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 29011