

4-6-88

To: 1 051032
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,126-0000

NE NW NE, SEC. 17, T 24 S, R 16 W 16 EX

4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5056

Lease Name Dutton Well # 1-17

Operator: F.G. Holl Company
Name & Address P.O. Box 780167
Wichita, KS 67207

County Edwards 143.65

Well Total Depth 4420 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 6 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4410' PBD 4388' Perfs at 4310-14'
1st plug sand back to 3260' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4, sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 p.m. Day: 6 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3260' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pumped 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

APR 11 1988

Maximum pressure 600 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 4-13-88

INV. NO. 20347