

1 030562

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,884-0000

NE NE SE, SEC. 22, T 24 S, R 16 (W/EX)

2046 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Skalsky Well # 3-22

Operator: F. G. Holl

County Edwards

Name &

Address 6427 East Kellogg

Well Total Depth 4385 142.51 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 6:00 pm Day: 28 Month: October Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4380' PBD 4363' Perfs at 4292-96'; 3821-25'

1st plug sand back to 3775' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:00 pm Day: 28 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3775' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 50 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION

Signed Steve Demont (TECHNICIAN)

DATE 11-1-85

NOV 1 1985

11-1-85

INV. NO. 10867

CONSERVATION DIVISION