

To: 1 051143  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-21 135 R  
API NUMBER 15-047-20,719-0000  
330' W of  
C E/2, SEC. 22, T 24 S, R 16 W 4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company

Name &

Address P.O. Box 780167

Wichita, KS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1989  
CONSERVATION DIVISION  
Wichita, Kansas

2640 feet from S section line

1650 feet from E section line

Lease Name Skalsky Well # 2-22

County Edwards 141.70

Total Depth 4360 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 21 Month: 3 Year: 1989

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4359' PBD 4319' Perfs at 3832-40'

1st plug sand back to 3770' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:50 a.m. Day: 21 Month: 3 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3770' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2390' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-27-89

INV. NO. 24230

Signed Richard M. Lacy (TECHNICIAN)