

To: 051140
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Operator: F.G. Holl Company

Name &

Address P.O. Box 780167

Wichita, KS 67207

3-21 137 R
API NUMBER 15- 047-21,196-0000

SE NE NE, SEC. 22, T 24 S, R 16 W&E

4290 feet from S section line

330 feet from E section line

Lease Name Skalsky Well # 4-22

County Edwards

Well Total Depth 4395 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 21 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4394' PBSD 4290' Perfs at 4246-60'

1st plug sand back to 4195' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 21 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4195' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2499' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard M. Lacy (TECHNICIAN)

DATE 3-27-89

INV. NO. 24232