

10-20-87

To: 1 061023  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,128-0000

SW NE SW, SEC. 32, T 24 S, R 16 W/X  
1650 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Kearstin Well # 2-32

Operator: F.G. Holl Company

County Edwards 147.06

Name & Address P.O. Box 780167

Well Total Depth 4525 feet

Wichita, KS 67278-0167

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 20 Month: 10 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4515' PBD 4338' Perfs at 4326-30'

1st plug pump 30 sx common cement to 4200',

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 20 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to 4200',

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 300 psi and shut in 150 psi.

OCT 22 1987  
10-22-87  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3241' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 10-28-87

INV. NO. 18684

10-20