

To: 1 090478  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-24

API NUMBER 15- 047-21,400 - 0000

NE NE NW, SEC. 32, T 24 S, R 16 W/E  
4950 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address: P.O. Box 8647  
Wichita, KS 67208

Lease Name Wood G Well # 1  
County Edwards 143.00  
Well Total Depth 4400 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Co. License Number 5142  
Address P.O. Box 129, Sterling, KS 67579-0129

Company to plug at: Hour: 5 a.m. Day: 24 Month: 9 Year: 19 94

Plugging proposal received from Vaughn Thompson  
(company name) Sterling Drilling Co. (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1112'  
1st plug at 1120' with 50 sx cement, 2nd plug at 700' with 50 sx cement,  
3rd plug at 290' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 7 a.m. Day: 24 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 1120' with 50 sx cement,  
2nd plug at 700' with 50 sx cement,  
3rd plug at 300' with 50 sx cement, *Rec'd*  
4th plug at 40' with 10 sx cement, *9-27-94*  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (client) do hereby observe this plugging.

DATE 9-29-94  
INV. NO. 41305

Signed *[Signature]* (TECHNICIAN)