

7-24

5
2-030584

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 155-20,136-0000

SE, SECTION 28 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5118 990 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR T G T Petroleum Corp.
NAME & 209 East William
ADDRESS Wichita, KS 67202

LEASE NAME: Smith Van-Buren #2
COUNTY: Reno
WELL TOTAL DEPTH: 3386' 110.04

PIPE: _____
SURFACE CASING: 10-3/4" @ 239'w/275 sx

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 19 MONTH: 7 YR: 1990
PLUGGING PROPOSAL RECEIVED FROM: Bill Shingle
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: TD 3386' - 5-1/2" @ 3339' w/75 sx openhole - sand to 3300' - cap w/5 sx - recover available pipe - 35' sx circ at 800' - 300' to surface - circ cmt.

AUG 17 1990
8-17-90
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING PROPOSAL RECEIVED BY: John Sanders
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (top) NONE (_____)
COMPLETED: HOUR: 14:30 DAY: 24 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Plugged back w/sand 3280' - capped w/5 sx cmt by bailer - shot pipe @ 2800'-2000' & recovered.
7/20/90- circ approx 35 sx cmt @ 870' - pulled out pipe to 334' - circ approx 130 sx - good circ but no cmt - let set - measured upon top of cmt. On 7/23/90, approx 110' dto 120' - refilled to surface w/3 yds slurry cmt.

REMARKS: Howco #000436-7 Haven Redi Mix #9758

I DID OBSERVE THIS PLUGGING.
INVOICED

DATE: 8-24-90
INV. NO. 2905.5

Merlan Unruh - Kee
Merlan Unruh (AGENT)

nk