

7-18  
2-100601

176  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 7/16/68 15-155-20059-0000  
SE NE SE, SECTION 28 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5118 FEET FROM S SECTION LINE  
FEET FROM E SECTION LINE

OPERATOR TGT Petroleum Corporation  
NAME & ADDRESS 209 East William  
Wichita, KS 67202

LEASE NAME: Smith Van Buren #1  
COUNTY: Reno 111.15  
WELL TOTAL DEPTH: 3420'  
CONDUCTOR PIPE: 5-1/2" @ 3420'/100 sx  
8-5/8" @ 735'/100 sx  
SURFACE CASING: 10-3/4" @ 226'/275 sx

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_  
OTHER WELL AS HEREINAFTER INDICATED: Perf 3306-12', 27-29', 36-41', 77-84'  
PLUGGING CONTRACTOR: Kelso Casing Pulling  
ADDRESS: Box 176, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 18 MONTH: 7 YEAR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Eldon  
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

HERE: Sand bottom 50' above top perf - 5 sx cmt - shoot & pull pipe (5-1/2") to 800' - circ 35 sx cmt - pull to 300' & circ to surface inside & outside 8-5/8" if cmt not at top of well.

PLUGGING PROPOSAL RECEIVED BY: John Sanders  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 12:00 DAY: 18 MONTH: 7 YEAR: 1990

23 1990  
CONSERVATION DIVISION  
Wichita, Kansas  
7-23-90

ACTUAL PLUGGING REPORT:  
Sand to 3250' 5 sx cmt - shot & pulled 5-1/2" from 2600' to 800' pumped 35 sx cmt & circulated - pulled all 5-1/2" out of hole - hooked swedge up to 8-5/8" - displaced 21 bbls water and 115 sx cmt from top to 800' - shut in well - cmt 8-5/8" & 10-1/2" off - welded nipple on 10-1/2" - pumped backside of 8-5/8" until full on 7/19/90. - Used 35 sx - shut-in @ 200#.

REMARKS: Howco #00047  
I DID OBSERVE THIS PLUGGING.

**INVOICED**

DATE: 7-30-90  
INV. NO. 28794  
7-18

John Sanders  
John Sanders (AGENT)