

4-18

2-

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-21285-0000  
NE NW SE, SECTION 33 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5330 2310 FEET FROM S SECTION LINE  
1650 FEET FROM E SECTION LINE

OPERATOR EXCALIBUR PRODUCTION CO  
NAME & P O BOX 278  
ADDRESS MCPHERSON KS 67460-0278

LEASE NAME: MCKEE #1  
COUNTY: RENO  
WELL TOTAL DEPTH: 3371'

PIPE: 13-3/8" @ 233'

SURFACE CASING: 8-5/8" @ 606'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: KELSO CASING PULLING INC  
ADDRESS: P O BOX 347, CHASE KS 67524-0347 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 18 MONTH: 4 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DENIS GORDLEY  
COMPANY NAME: EXCALIBUR PRODUCTION CO INC PHONE: 316-242-7156

WERE: SAND TO 3300' & TOP W/5 SX CMT - SHOOT 5-1/2" CSG OFF  
& PULL SAME - TIE ON TO 8-5/8" CSG & PMP 400 LBS HULLS,  
10 SX GEL, 8-5/8" WIPER PLUG & 180 SX CMT - SHUT WELL  
INE - 13-3/8" @ 233' W/250 SX - 8-5/8" @ 606' W/488 SX  
- 5-1/2" @ 3349' - OH 3349' TO 3371'

PLUGGING PROPOSAL RECEIVED BY: M L KORPHAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 16:30 DAY: 18 MONTH: 4 YEAR: 1994

ACTUAL PLUGGING REPORT:  
SANDED TO 3300' & TOPPED W/5 SX CMT - SHOT PIPE OFF  
AT 2649' & PULLED SAME - TIED ON TO 8-5/8" CSG & PUMPED  
400 LBS HULLS, 10 SX GEL - 8-5/8" WIPER PLUG & 180 SX  
CMT - MAX PRESS 500 LBS - SHUT IN WELL, 300 LBS -  
RETRIEVED 2649' OF 5-1/2" CSG

REMARKS: 60/40 POZ W/6% GEL - ALLIED #6336

I DID OBSERVE THIS PLUGGING.  
**INVOICED**

DATE 4-25-94  
INV. NO. 40326

*[Handwritten signature]*

Michael R. Wilson (AGENT)

**RECEIVED**  
KANSAS CORPORATION COMMISSION

APR 20 1994

CONSERVATION DIVISION  
WICHITA, KS 67202  
REV. 3/90

109.55

4-20-94