

7-18

REC
KANSAS CORPORATION COMMISSION

2-010078

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

AUG 02 1995

8-2-95

CONSERVATION DIVISION
API NUMBER: WICHITA, KS 155-20,042-0000

SW, SE, NE, SECTION 33 TOWNSHIP 23 RANGE 4W

OPERATOR LICENSE # 5330 2970 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR EXCALIBUR PRODUCTION CO. INC.
NAME & P.O. BOX 278, 1016 N. MAIN
ADDRESS MCPHERSON, KS 67460

LEASE NAME: DAISEY E. PIERCE #3
COUNTY: RN *Renol*
WELL TOTAL DEPTH: 3677' *119.50*

PIPE: _____

SURFACE CASING: 10" @ 247'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE KELSO TESTING & SALVAGE
ADDRESS: P.O. BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 11:30 DAY: 17 MONTH: 7 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: DENNIS GORDLY
COMPANY NAME: EXCALIBUR PRODUCTIN CO. INC. PHONE: 316-241-1265
WERE: SAND TO 3290' AND TOP WITH 10 SKS. CMT. SHOOT PIPE OFF
AND PULL SAME TO 600'. SPOT 35 SKS. CMT. PULL PIPE TO
375' AND CIRCULATE CMT. TO SURFACE. PERFORATIONS @
3348'-3353'; 5 1/2" CASING @ 3672'.

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 14:00 DAY: 18 MONTH: 7 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED TO 3290' AND TOPPED WITH 10 SKS. CMT. SHOT
PIPE OFF @ 897'. PULLED PIPE TO 613' AND SPOTTED 35
SKS. CMT. PULLED PIPE TO 390' AND CIRCULATED 175 SKS.
CMT. CEMENT DID NOT COME TO SURFACE. RAN WIRELINE TO
TOP OF CMT. @ 244'. RAN 2" TUBING TO TOP OF CMT. AND
CIRCULATED 100 SKS. CMT. TO SURFACE.

REMARKS: USED 60/40 POXMIX W/4% GEL BY ALLIED #2834 & #2835.

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson (AGENT)

INVOICED

DATE 8-7-95
INV. NO. 43249
7-18

FORM CP-2/3
REV. 3/90