

2 040165

API NUMBER 15-095-01077-000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 SE/SE, SEC. 29, T. 28 S, R. 5 W/4

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111 5310 ^{1 cc} ₃₋₃₀₋₂₈₄

Lease Name Moorehouse Well # 3

Operator Name & Address Four Way Operating

County Kingman 127.44

Address P.O. Bx 698

Well Total Depth 3921 feet

Great Bend Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 255 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Bx 698 Great Bend 67530

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from D.-B. Pulley

(company name) Rockhold Engineering (phone) _____

were: SB to 3760 and 4 SKS

4 1/2 3929 150 SK 3 Halls 15 sec RESEED 60/40 3% CAC

Perf. 3863-70 Rec 3100'

STATE CORPORATION COMMISSION
RESEED 60/40 3% CAC

FEB 12 1985
2-12-85
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1415 Day: 4 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT Sand was dumped down the well to sand off the perforations to 3760' and 4 sacks of cement was spotted on top of sand with dump bailer. The pipe was shot off and pulled, 3100' of 4 1/2" casing was recovered. The top was squeezed by pumping 3 sacks of Halls, 15 sacks of gel and 150 sacks of 60/40 Pz 3% CAC

Remarks: Allied Cementing Ticket # 1883 MX 200 3I 50
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.)

DATE 2-13-85

Signed Stan Marcotte
(TECHNICIAN)

INV. NO. 6968 talked about this

RC