

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-188-02094-0000

LEASE NAME Blake #10

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SW NW SE

SEC. 23 TWP. 23 RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed \_\_\_\_\_

Plugging Commenced 8/1/85

Plugging Completed 8/1/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR S & K Oil Co.

ADDRESS Box 559, Tulsa, OK. 74101

PHONE # (918) 587-4159 OPERATORS LICENSE NO. 5217

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5008'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/4	306'	none
				10 3/4	700'	none
				7"	3830'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only - No pipe recovery. Ran tubing to 3800', spotted 50 sacks cement, pulled tubing to 3300' & spotted 50 sacks cement, waited one hour, spotted 25 sacks cement, 7" plug, 7 sacks gel, & 3 hulls. Pulled 20 joints, spotted another 25 sacks cement, pulled all tubing out of hole. Shot 7" casing @ 289'. Tied on to 7", pumped 75 sks. cement. Cement circulated around through 10 3/4. (60/40 poz 2% gel 3% c.c.) Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of August, 1985

STATE CORPORATION COMMISSION

Notary Public

AUG 7 1985

8-9-1985

CONSERVATION DIVISION Form CP-4  
Wichita, Kansas Revised 01-84

My Commission expires:



15-155-02094-0000

DRILLERS LOG

Blake #10  
 Commenced R.D.: 5-8-55  
 Completed R.D.: 6-30-55  
 Total Depth: 5008'  
 Casing Record: 306'; 13 3/8"  
 700'; 10 3/4"

SW NW SE, Sec. 23-23-4  
 Reno County, Kansas  
 Elevation: 1464 G.L.  
 Initial Prod.: Hunton Lime  
 Contractor: Buick Drilling Inc.

STRATA	DEPTH
Sand and gravel	0 - 165
Blue Shale	165 - 476
Salt and shells	475 - 490
Anhydrite and gyp	490 - 550
Gyp, lime and shells	550 - 702
Shale, lime and sand	702 - 895
Sand and lime	895 - 940
Lime and shale	940 - 970
Lime	970 - 1020
Broken Lime	1020 - 1205
Lime	1205 - 1300
Shale and lime	1300 - 2568
Lime	2568 - 2870
Shale and lime	2870 - 3200
Lime	3200 - 3210
Shale	3210 - 3253
Chert and lime	3253 - 3263
Chert	3263 - 3285
Chert and lime	3285 - 3386
Lime	3386 - 3425
Cherty lime	3425 - 3450
Chert	3450 - 3460
Lime	3460 - 3485
Shale and lime	3485 - 3520
Shale	3520 - 3605
Lime and chert	3605 - 3625
Cherty lime and shale	3625 - 3660
Shale and lime	3660 - 3750
Sand and shale	3750 - 3785
Shale and lime	3785 - 3815
Shale	3815 - 3820
Arbuckle lime	3820 - 3845
Lime	3845 - 3985
Lime and chert	3985 - 4035
Lime	4035 - 4170
Lime and chert	4170 - 4315
Lime	4315 - 4450
Granite Wash	4450

DST - 3356 to 3386

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 08 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.  
*H. R. Buick*  
 H. R. Buick, President

Signed and sworn to in my presence this first day of July, 1955, by H. R. President of the Buick Drilling Inc.

*Roberta Shogren*  
 Notary Public

My commission expires December 26, 1955.