

15-155-00149-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit,  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Reno County, Sec. 23 Twp. 23 Rge. (E) 4 (W)

Location as "NE/CNW&SW" or footage from lines NW/4 NW/4 SW/4  
Lease Owner George Siegrist  
Lease Name Krahdial (Wilson) Well No. 1  
Office Address Hutchinson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 19 19 53  
Application for plugging filed September 19 19 53  
Application for plugging approved September 19 19 53  
Plugging commenced September 19 19 53  
Plugging completed September 19 19 53  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3628 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	259.19'	None
				(Cemented top to bottom)		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3628 feet to 0 feet for each plug set.

Filled hole with heavy rotary mud to 255'.  
Set a bridging plug at 255'.  
Placed 1/2 sack of hulls on top of bridging plug.  
Placed 15 sacks of cement on top of hulls.  
Filled hole with heavy rotary mud to 40'.  
Set a bridging plug at 40'.  
Placed 1/2 sack of hulls on top of bridging plug.  
Placed 10 sacks of cement on top of hulls to top of ground.

9-24-1953

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1953  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Drilling Company  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
O. G. STEARNS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. G. Stearns  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of September, 19 53

My commission expires March 3, 1957  
Zita Henning Notary Public.

PLUGGING  
FILE SEC 23-23-R4w  
BOOK PAGE 120 LINE 22

KRAHDIAL #1 WELL  
(WILSON)

15-155-06149-0000

Operator: George Siegrist  
 Contractor: Stearns Drilling Company  
 Commencement Date: September 2, 1953  
 Completion Date: September 20, 1953

Location: NW NW SW  
 Section 23-23-4,  
 Reno County, Kansas.

Casing Record:

8 5/8" 259.19' Cemented with 175 sacks.

WELL LOG

Cellar	0	5
Surface Clay	5	80
Sand	80	100
Sand and Shale	100	257
Shale	257	500
Lime and Shale	500	995
Lime	995	1050
Lime and Shale	1050	1765
Shale	1765	1860
Lime and Shale	1860	2235
Lime	2235	2255
Lime and Shale	2255	2560
Lime	2560	2675
Lime and Shale	2675	3080
Lime	3080	3142
Shale	3142	3277
Shale and Chert	3277	3348
Dolomite	3348	3356
Chert	3356	3498
Shale	3498	3533
Shale and Lime	3533	3575
Shale	3575	3614
Lime	3614	3628
Total Depth:	3628	

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF RUSSELL )

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 24 1953  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

Harold Hubbard

SUBSCRIBED AND SWORN to before me, a Notary Public, this 23rd day of September, 1953.

John Deering

My Commission Expires:

March 3, 1957

PLUGGING  
 FILE SEC 23-23-R-40  
 BOOK PAGE 120 LINK 22