

15-095-20112-000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman

County. Sec. 5 Twp. 28S Rge. (E)6 (W)

Location as "NE/CNW/SE/SW" or footage from lines C SE NW

Lease Owner Kaiser-Francis & Prospect Oil, Inc.

Lease Name KAUFMAN Well No. 1

Office Address 811 Union Center - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-11 19 68

Application for plugging filed 8-11 19 68

Application for plugging approved 8-11 19 68

Plugging commenced 8-11 19 68

Plugging completed 8-11 19 68

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4325 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud back to 245', spotted 1/2 sack hulls, plug and 25 sacks cement. Mud back to 40', spotted 1/2 sack hulls, solid bridge and 10 sacks cement. Completed at 10:45 PM, 8-11-68.

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1968
CONSERVATION DIVISION
Wichita, Kansas
8-15-68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of August, 19 68

My commission expires 6-30-71 Sherry Gish Notary Public.

15-095-20112-0000

ROTARY DRILLING LOG

Operator: Kaiser-Francis and
Prospect Oil, Inc.
KAUFMAN #1
C SE NW Sec. 5-28S-6W
Kingman County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 8-1-68
Completed: 8-11-68
Remarks: Set 8-5/8" casing
@ 252' with 225 sx.

Formations

Sand	20'
Red Bed and Shale	252'
Shale	728'
Anhydrite (Broken)	1200'
Lime and Shale	1785'
Shale and Lime	2200'
Lime and Shale	2430'
Shale	2670'
Lime and Shale	2915'
Lime, Shale and Sand	3130'
Lime	3882'
Lime with Chert	3912'
Lime	4202'
Shale	4260'
Lime	4283'
Lime and Shale	4325'
Rotary Total Depth (D & A)	4325'


RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 13th day of August, 1968.


Sherry Gish Notary Public

My Commission Expires:
June 30, 1971