


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 7 Twp. 28S Rge. (E) 6 (W)  
Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner Pickrell Drilling Company  
Lease Name Greenleaf "C" Well No. 1  
Office Address 705 4th Natl. Bank Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 23, 19 65  
Application for plugging filed December 23, 19 65  
Application for plugging approved December 23, 19 65  
Plugging commenced December 23, 19 65  
Plugging completed December 23, 19 65  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4255 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 201'   | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200', set plug, cemented with  
25 sacks cement. Heavy mud to 40', set plug,  
cemented with 10 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 6 1966  
1-6-66  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pickrell Drilling Company  
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits  
705 4th National Bank Bldg, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 28th day of December, 19 65

My commission expires June 21, 1966  
Maxine Blackman, Notary Public.



**ROTARY DRILLING LOG**

15-095-30250000

COMPANY: PICKRELL DRILLING COMPANY,  
705 4th National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 12-9-65  
Rotary Drilling Completed 12-22-65

LOCATION: Greenleaf "C" No. 1, C NW NW Section 7-28-6W, Kingman County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" surface casing set at 200', cemented with 150 sacks cement. Circulated. Completed 1:45 P.M. December 9, 1965. No oil string run. D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

|      |                       |                    |
|------|-----------------------|--------------------|
| 18   | Sand                  | <u>C. F. S.</u>    |
| 335  | Red Bed               | 2870               |
| 900  | Shale & Shells        | 3095               |
| 2730 | Lime & Shale          | 3385               |
| 3055 | Lime, Sand & Shale    | 3445               |
| 3115 | Lime                  | 3470               |
| 3218 | Lime & Shale          | 3511               |
| 3278 | Lime                  | 3516               |
| 3340 | Kansas City           | 3798               |
| 3405 | Lime & Shale          | 3820               |
| 3445 | Lime                  | 3830               |
| 3470 | Kansas City           | 3845               |
| 3605 | Lime                  | 4171               |
| 3675 | Lime & Shale          | 4180               |
| 3830 | Shale & Mississippian | 4190               |
| 3845 | Mississippian         | 4195               |
| 3910 | Mississippian         | 4199               |
| 3975 | Lime                  | 4205               |
| 4005 | Mississippian         | 4211               |
| 4077 | Lime                  | 4225               |
| 4183 | Shale & Lime          | 4255               |
| 4199 | Sand                  |                    |
| 4207 | Viola Top             | <u>Slope Tests</u> |
| 4217 | Viola                 | 2500               |
| 4255 | Sand - RTD            | 3000               |
|      |                       | 3500               |
|      |                       | 4000               |
|      |                       | <u>S. L. M.</u>    |
|      |                       | 3095               |
|      |                       | 3647               |
|      |                       | 4178               |

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 6 1966  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 28th day of December, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

[Signature]  
Maxine Blackman, Notary Public