


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 9 Twp 28S Rge. 6 (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines Center NE NE
Lease Owner Donald T. Ingling, et al
Lease Name Galkins Well No. 1
Office Address 615 First National Bk Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 29 19 68
Application for plugging filed Verbal Approval 19 68
Application for plugging approved Verbal Approval 19 68
Plugging commenced May 29 19 68
Plugging completed May 29 19 68
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	217	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,444 feet (rotary total depth) to 210 feet. Set plug at 210 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1968
CONSERVATION DIVISION
Wichita, Kansas
6-4-68

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main St., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main St., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 68

My commission expires April 21, 1971
Martha Hartpence Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-095-20089-0000

COMPANY Donald T. Ingling, et al

SEC. 9 T. 28S R. 6W

FARM Calkins

NO. 1

LOG. C NE NE

TOTAL DEPTH 4,444'

COUNTY Kingman


COMM. May 13, 1968

COMP. May 29, 1968

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10		
15	8-5/8"	217' cemented w/165 sx cement	ELEVATION 1,554 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Clay	100		<u>ELECTRIC LOG TOPS</u>
Red Bed	218		
Shale & Shells	820	Topeka	2524 - 970
Shale	916	Heebner	2894 - 1340
Shale & Lime	1515	Douglas	2946 - 1392
Lime & Shale	1650	Lansing - K.C.	3145 - 1591
Shale & Lime	1790	Mississippi	3915 - 2361
Lime & Shale	2315	Kinderhook	4248 - 2694
Shale & Lime	2615	Meisner	4316 - 2762
Lime	2732	Viola	4338 - 2784
Lime & Shale	2915	Simpson	4363 - 2809
Shale & Lime	3180	Log T.D.	4444 - 2890
Lime	3820	Rotary T.D.	4444 - 2890
Shale & Lime - Cherty	3870		
Lime & Shale	3925		
Chert	3952		
Lime	4236		
Lime & Shale	4339		
Lime	4373		
Sand	4444		
Rotary Total Depth	4444		

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd day of June, 1968.

Martha Hartpence
 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971