

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-155-20049-0000 (of this well)

Operator's Full Name Dunbar Drilling, Inc.

Complete Address 5252 North Broadway, Wichita, Kansas 67219

Lease Name Johnson "B" Well No. 1

Location SE SE NE Sec. 5 Twp. 24 Rge. 4 (E) (W)X

County Reno Total Depth 3410'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Operator and Allied Cementing Co.

Address     

RECEIVED  
License No.       
STATE CORPORATION COMMISSION

Operation Completed: Hour 3 PM Day 2 Month April Year 1976

APR 14 1976

The above well was plugged as follows:

CONSERVATION DIVISION

Hole filled with sand to 3350' and cemented with Wichita, Kansas cement.

Hole squeezed with 5 sacks hulls, 30 sacks gel-mud, 100 sacks cement,  
10 sacks gel-mud, 5 sacks hulls, and 100 sacks cement w/3% calcium-  
chloride.

Surface casing had parted in lost circulation zone (approx. 480') and  
a large area around the location had sunk and had to be filled with dirt.

8-5/8" surface casing was set at 600' with 400 sacks cement behind it.  
2504' of 5 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: Stelbush J. Loman  
Well Plugging Supervisor

INVOICED

DATE 4-14-76

INV. NO. 3066-W