

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-155-20, 773-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name AFrico Explorations, Inc., Ltd.

Complete Address 122 North Greenwood, Tulsa, Oklahoma 74120

Lease Name Johnson "B" Well No. 4

Location SW SE NE Sec. 5 Twp. 24 Rge. 4 (~~East~~) (West)

County Reno Total Depth 480'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Lost Hole (Lost circulation in salt)

Plugging Contractor (H-30, Inc. Tools) Nicholas Casing Pulling & Halliburton Co.

Address Box 373, Geneseo, Kansas License No. 711

Operation Completed: Hour: 7:00 PM Day: 29 Month: September Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

Ran 2" tubing to 372' and pumped 100 sacks cement through tubing at 372'. Pulled tubing to 252'. Pumped 100 sacks cement through tubing at 252'. Tubing stuck. Backed off 3 Joints tubing and pulled 3 Joints leaving 5 Joints in hole at approximately 50'. Ran 64' of 4 1/2" casing to 56'. Circulated 4 1/2" inside and out with cement.

Amount of Surface Casing: 4 1/2 - 56' circ.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

Signed: _____
Conservation Division Agent

OCT 05 1982

CONSERVATION DIVISION
Wichita, Kansas

INVOICED


DATE 10-18-82

AMOUNT 1367.40

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1982
FIELD REPORT

CONSERVATION DIVISION
Wichita, Kansas

DATE. 9-22-82
OPERATOR. H. Eric Explorations Inc., Ltd.
LEASE. Johnson "B"
LOCATION. SEC. 5 . TWP. 24 . RGE. 4
COUNTY. Reno



REMARKS. (WHAT WAS SAID OR SEEN).

Drill collars left in hole when circulation was lost in salt at app. 480'. 9-22-82 moved in Nicholas casing pulling Genesee, Kansas. Rigged up on collars. 9-23-82 worked collars. 9-24-82 Pulled 3 1/2 collars 9-27-82 Pulled 3 collars 9-28-82 Pulled 3 collars. Hung up in Equis. Beds sand. Washed down to bit. w/ 2 3/8" tubing and 25 sacks gel-mud. 9-29-82 Pulled 3 collars - Sub - 13 3/8" bits. Total 380'. Found out that they had already pulled 2 Joints drill pipe and 1 1/2 collars before they moved H-30 Drilling, Inc's rig off of hole. Washed back down to 372' using 2" tubing and 25 sacks gel-mud. Pumped 100 sacks common cement through tubing at 372'. Pulled tubing to 252'. Pumped 100 sacks common cement through tubing at 252'. Tubing stuck. Unscrewed 3 Joints leaving 5 Joints in hole at app. 90' (Top.) Set 64' of 4 1/2" casing at 56'. Circulated with cement inside and out. Job completed at 7:00 PM 9-29-82. - Left location at 8:00 PM after setting cellar. Bottom of sand at approx 140'

FOR THE STATE. [Signature]

KANSAS CORPORATION COMMISSION
202 W. 1st St. 200 COLORADO DERBY BLDG.
WICHITA, KANSAS 67202



**BULK MATERIALS DELIVERY
AND
TICKET CONTINUATION**

15-155-20773-0000

FOR INVOICE AND
TICKET NO.

DATE 9-29-82	CUSTOMER ORDER NO.	WELL NO. AND FARM 4-Johnson	COUNTY Renov	STATE Kansas
CHARGE TO Africa Exploration, Inc., LTD		OWNER Same	CONTRACTOR No. B 115409	
MAILING ADDRESS 2225 E. 21st. Street, suite 205		DELIVERED FROM El Dorado, Ka.	LOCATION CODE 50305	PREPARED BY Mooney-Pick up Stackley Fisher
CITY & STATE Wichita, Kansas		DELIVERED TO Loc.	TRUCK NO. 0513	RECEIVED BY

PRICE REFERENCE	SECONDARY REF. OR PART NO.	CODE		DESCRIPTION	UNITS 1		UNITS 2		UNIT PRICE	AMOUNT
		L	D		QTY.	MEAS.	QTY.	MEAS.		
501-043		2	B	Reg. Portland	300	Sk.			4.85	1455.00
509-554		2	B	Halliburton Gel Co On The Side	25	Sk.			6.30	157.50
<p>RECEIVED STATE CORPORATION COMMISSION OCT 05 1982 CONSERVATION DIVISION Wichita, Kansas</p>										
				Returned Mileage Charge						
				TOTAL WEIGHT		LOADED MILES		TON MILES		
				SERVICE CHARGE ON MATERIALS RETURNED				CU. FEET		
500-307		2	B	SERVICE CHARGE				300	.95	285.00
500-306		2	B	Mileage Charge	30.700	70		1074.5	.70	752.15
				TOTAL WEIGHT		LOADED MILES		TON MILES		
No. B 115409		CARRY FORWARD TO INVOICE					SUB-TOTAL			

