

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1978
10-13-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 095-20584-0000 (of this well)

Operator's Full Name Leas Pet. Co.
Complete Address 1325 Dickson St. Bldg. Wichita, Kans - 67202
Lease Name Clouse Well No. 1
Location C-NE-NE- Sec. 12 Twp. 28^S Rge. 6 (E) (W) X
County Fingerman Total Depth 3847
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Felso Casing Pulling
Address Box 176 - Chase, Kans. 67524 License No. 683
Operation Completed: Hour 12-11 Day 12 Month 10 Year 1978

The above well was plugged as follows:

218' 8 5/8" Casing w/ 175 sack Cement - 5 1/2" Casing set @ 3846' w/
125 sack Cement - Top prof. 3817' Allied mixed & pumped
40 sack Cement, Cement in 5 1/2" Casing - release plug - pump
plug to 3605' Shut in w/ 2300# pressure Pull: 3028' 5 1/2"
Casing - Allied mixed & pumped. 3 sack bulls - 20 sack gel
release plug - mixed & pumped 100 sack 60/40 gas Cement
w/ 37 gel to top of Casing - shut in w/ 500# pressure -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10-13-78
INV. NO. 8292-W