

15-09500110000

Form CP-3  
Rev. 6-26-62

*W*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 8 1963  
8-8-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Don F. Moore

Complete Address: 918 Central Bldg., Wichita, Kansas

Lease Name Fay Well No. # 1

Location SW NE Sec. 15 Twp. 28 Rge. 6 (E) (W) W

County Kingman Total Depth 4260

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 6th Month August Year 1963

The Above well was plugged as follows:

211' of 8 5/8" surface pipe, cemented with 175 sacks. 4018' of 5 1/2" long  
string, cemented with 100 sacks. Plugged back to 3885'. Top perforation  
3881'. Sanded to 3870', cemented with 5 sacks. Hole was filled with mud  
to 250', 10' rock bridge, cemented with 20 sacks. Hole was filled with  
mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.  
3780' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/8/63  
INV. NO. 7536-W