


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Reno County, Sec. 5 Twp. 24S Rgs. 4W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner Dunbar Drilling Inc.  
Lease Name Johnson Well No. "B"-1  
Office Address 5252 N. Broadway Wichita, Ks. 67219  
Character of Well (completed as Oil, Gas or Dry Hole) depleted oil well  
Date well completed March 14 19 68  
Application for plugging filed 12-19 19 75  
Application for plugging approved 12-19 19 75  
Plugging commenced 12-19 19 75  
Plugging completed 12-19 19 75  
Reason for abandonment of well or producing formation depleted oil well

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3410 feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2503.85'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand back to 3340' & dump 5 sax. of cement. Shot well at 2811', 2716', 2641' and 2504'. Mixed 5 hulls, 30 gal. gel, 100 sax. of cement, waited 2 hours, put in 50 sax. cement, in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DUNBAR DRILLING INC.  
Address 5252 North Broadway Wichita, Kansas 67219

STATE OF Kansas COUNTY OF Sedgwick  
W. P. Simmons (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

Subscribed and sworn to before me this 12th day of May 19 76

Nov. 19, 1977

Frances J. Simmons Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1976

CONSERVATION DIVISION  
Wichita, Kansas

5-13-76

GEOLOGICAL REPORT

Drilling Contractor: Wofford Drlg. Co. Wofford Oil Co. Johnson "B" 1  
 Drilling Commenced: March 5, 1968 SE SE NE Sec. 5-24-4w  
 Drilling Completed: March 14, 1968 Reno County, Kansas

Gentlemen:

Following is the geological report on the captioned test well. Circulation was partially lost at 2845 feet and remained so to the total depth. However, the drilling time and samples were used to correlate with other wells and appeared to check out favorable. Measurements were taken from the Kelly Bushing.

Elevation: 1479' K.B.  
 Surface Pipe: 8 5/8" @ 600' with 400 sacks.  
 Production Pipe: 5 1/2" @ 3409' with 125 sacks.

Formation Summary

Cherokee	3209 (-1730)
Mississippian	3313 (-1834)
Total Depth	3410 (-1931)

SAMPLE DESCRIPTIONMississippian

- 3313 - 3332 Limestone; cream-buff, fine to medium crystalline, slightly dolomitic and cherty, poor porosity, no shows.
- 3332 - 3345 Limestone; buff, fine crystalline to partly chalky, with white and gray fresh chert, poor visible porosity, no shows.
- 3345 - 3356 Chert; gray and white, slightly weathered with pinpoint porosity, some tan sucrose dolomite, scattered light stain.
- 3356 - 3365 Chert; same as above, partly tripolitic.
- 3365 - 3376 Chert; white, fresh to tripolitic, good porosity, scattered light staining.
- 3376 - 3390 Chert; mostly barren, very slight shows.

Total Depth 3410 feet.

The Chert zone below 3345' carried oil shows and should be tested thru perforations.

Very truly yours,

*Lee Poulsen*  
 Lee Poulsen

RECEIVED  
 FEB 23 1975

CONFIDENTIAL  
 V. H. H. H. H. H.