

STATE OF KANSAS STATE CORPORATION COMMISSION 200 Colorado Derby Bldg. Wichita, Kansas 67202


FEB 17 1983

CONSERVATION DIVISION Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit

COUNTY RENO SEC. 5 TWP. 24 RGE. 4w E/W Location as in quarters or footage from lines: C N/2 S/2 SE/4



Locate Well correctly on above Section Platt.

Lease Owner EXCALIBUR PRODUCTION CO., INC. Lease Name TETEN Well No. 3 Office Address 523 W. KANSAS McPHERSON, KS. 67460 Character of Well (Completed as Oil, Gas or Dry Hole): OIL Date Well Completed 6-9-81 Application for plugging filed 2-8-83 Plugging commenced 2-11-83 Plugging completed 2-15-83 Reason for abandonment of well or producing formation DRY

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MAURICE V. LESLIE Producing formation Depth to top bottom T.D. 3364' Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled Out. Row 1: 4 1/2", 2,505.00

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SET PLUG AND SAND BACK TO 3300' WITH 6 SACKS OF CEMENT

ALLIED CAME OUT AND PUMPED DOWN 15 SACKS OF JELL; 6 SACKS OF HULLS; 10 SACKS JELL; PUSHED DOWN RUBBER PLUG; AND 100 SACKS OF COMMON CEMENT WITH 3% C.C. HAD MAX. PRESSURE OF 500 LBS. SHUT IN WITH 200 LBS.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor H&H CASING PULLING CO. 1427 N. HALSTEAD HUTCHINSON, KS. 67501

STATE OF KANSAS COUNTY OF RENO, ss. DONALD H. HURST (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald H. Hurst 2900 ACRES RD. APT. 107; HUTCHINSON, KS. 67501 (Address)

SUBSCRIBED AND SWORN to before me this 15 day of February, 19 83 Madeline Hurst Notary Public.

My Commission expires: 2-10-85





RECEIVED
STATE CORPORATION COMMISSION

Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

FEB 9 1983

CONSERVATION DIVISION
Wichita Kansas

June 15, 1981

COMPANY: EXCALIBUR PRODUCTION CO., INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: TETEN #3
 LOCATION: C N/2 S/2 SE/4 Section 5-24-4W,
 Reno County, Kansas
 COMMENCED: June 9, 1981
 COMPLETED: June 15, 1981
 ELEVATION:

API NO. 15-155-20,803-0000

0	to	225	Sand
225	to	255	Clay
255	to	290	Shale
290	to	815	Shale & Lime
815	to	1725	Lime & Shale
1725	to	2215	Shale & Lime
2215	to	3045	Lime & Shale
3045	to	3195	Lime
3195	to	3305	Lime & Shale
3305	to	3324	Shale & Lime
3324	to	3368	Mississippi
		3368	T. D.

Cut 12 1/2" hole to 285' and run 287' of 8 5/8" surface casing, cemented with 100 sacks of cement at 285'. Plug down at 11:00 A. M., June 9, 1981. Run 3399' of 5 1/2" casing, cemented with 75 sacks of cement at 3364', 4 feet off bottom at 3364'. Plug down at 1:45 A. M., June 15, 1981.

TOPS: MISSISSIPPI - 3324'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of your log on the Teten #1, located on the C N/2 S/2 SE/4 Section 5-24-4W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 15th day of June, 1981.

Johnnie L. Schmidt - Notary Public

