

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

155

API NUMBER 15-185-20365-0070

LEASE NAME Morentha Miller #1

WELL NUMBER _____

SPOT LOCATION SW/4 SE/4 SW/4

SEC. 5 TWP. 24 SRGE. 4w (E) or (W)

COUNTY Reno

Date Well Completed 2/14/77

Plugging Commenced 3/11/85

Plugging Completed 3/14/85

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS P.O. Box 278, McPherson, Ks. 67460

PHONE #(316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3365'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 283' | none |
| | | | | 5 1/2" | 3351' | 2015' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3300' & 6 sacks cement. Shot pipe at 3014', 2500', & 2015'. Pulled 61 joints of pipe. Baled hole to 350' & set Rock Bridge, dumped 6 yards Ready-mix.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
STATE CORPORATION COMMISSION

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

MAR 22 1985
3-22-85
CONSERVATION DIVISION
Wichita, Kansas


COPY

SUBSCRIBED AND SWORN TO before me this 18 day of March, 19 85



My Commission expires:

Irene Hoover
Notary Public



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

February 15, 1977

COMPANY: EXCALIBUR PRODUCTION CO., INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MORETHA H. MILLER #1
 LOCATION: SW/4 SE/4 SW/4, Sec. 5-246-4W,
 Reno County, Kansas
 COMMENCED: February 5, 1977
 COMPLETED: February 14, 1977
 ELEVATION: TO 3365'

| | | | |
|------|----|------|--------------|
| 0 | to | 250 | Sand |
| 250 | to | 285 | Blue Shale |
| 285 | to | 915 | Shale & Lime |
| 915 | to | 1175 | Lime |
| 1175 | to | 1420 | Lime & Shale |
| 1420 | to | 1800 | Shale & Lime |
| 1800 | to | 2130 | Lime & Shale |
| 2130 | to | 2425 | Lime |
| 2425 | to | 2680 | Shale & Lime |
| 2680 | to | 2970 | Lime |
| 2970 | to | 3075 | Lime & Shale |
| 3075 | to | 3326 | Shale & Lime |
| 3326 | to | 3365 | Mississippi |
| | | 3365 | T. D. |

Cut 12 1/2" hole to 283' and run 285' of 8 5/8" surface pipe, cemented with 300 sacks of cement at 283'. Plug down at 1:00 P. M., February 5, 1977. Drilled 7 7/8" hole to 3365'. Run 3375' of 5 1/2" casing, cemented with 50 sacks of cement at 3351', 14 feet off bottom. Plug down at 2:30 P. M., February 14, 1977.

TOPS: MISSISSIPPI - 3326'

Measurements taken from K. B.

CERTIFICATE

Johnnie E. Schmidt, Geologist

JOHNNIE E. SCHMIDT
 Sumner County, Ks.
 My Comm. Exp. June 29, 1977

Open hole 3351' to 3365'

Geological Survey Division

2011 S. 2nd St.

McPherson, Kansas 67460