

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County, Sec. 4 Twp. 24 Rge. 4 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' from
South line; 330' from East line, SE SE NW

Lease Owner Sterling Drilling Company
Lease Name Gilbert Well No. 1

Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole)

Oil Well

Date Well completed August 8, 1967 19
Application for plugging filed September 6, 1979 19
Application for plugging approved Sept. 7, 1979 19
Plugging commenced Sept. 28, 1979 19
Plugging completed Sept. 28, 1979 19
Reason for abandonment of well or producing formation

Tubing parted and stuck in hole

If a producing well is abandoned, date of last production
March 16, 1979 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Mississippi Depth to top 3306' Bottom 3357' Total Depth of Well 3357'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	569	8 5/8"	569	0
Mississippi	Oil and Water	0	3335	4 1/2"	3335	0
		0	3354	2 3/8"	3354	474'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pumped 10 sacks 50/50 Pozmix cement with 2% gel
in 4 1/2" casing. Pumped 1 sack hulls and 50 sacks
50/50 Pozmix cement with 2% gel in annulus between
8 5/8" and 4 1/2". Pumped 4 sacks gel and 28 sacks
50/50 Pozmix cement with 2% gel in 4 1/2" casing.
Job complete 11:00 AM, 9-28-79. Mixed and pumped by
Allied Cementing Company.

RECEIVED
STATE CORPORATION COMMISSION
OCT - 5 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 79

NOTARY PUBLIC
KANSAS
CHARLES M. HALL
Rice County, Ks.
My Appt. Exp. Jan. 31, 1982

Charles M. Hall
Charles M. Hall, Notary Public.

My commission expires _____

Group Exploration Company
Sterling, Kansas

Well Log ----- Gilbert #1
 Located: SE SE NW Section 4-24S-4W, Reno County, Kansas

Owner: Sterling Drilling Company, et al
 Rotary Drilling Contractor: Group Exploration Company

Commenced: June 30, 1967
 Completed: July 7, 1967

Rotary Total Depth: 3339'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 220	Sand & Gravel	Run 12 joints 8-5/8" (556.49') set at 569' with 350 sacks SUN SET cement. Plug was down at 10:45 p.m..
220 - 570	Clay, Shale & Sand	
570 - 700	Anhydrite & Shale	
700 - 1005	Shale, Sand & Lime	
1005 - 2225	Lime & Shale	
2225 - 2360	Lime	
2360 - 2690	Shale & Lime	
2690 - 3070	Lime	
3070 - 3299	Shale & Lime	
3299 - 3339	Mississippi Lime T.D.	Run 102 joints 4-1/2" casing (3329.05) threads off. 3040.08' 4-1/2" #J55 8 RN. SS (B condition) 288.98' 9-1/2" #J-55 8 RN. SS (A condition)) Set at 3335' with 75 sacks common cement. Job completed at 10:20 p.m..

RECEIVED
 STATE CORPORATION COMMISSION
 SEP - 7 1979
 CONSERVATION DIVISION
 Wichita, Kansas

Group Exploration Company
Sterling, Kansas

Well Log ----- Gilbert #1
Located: SE SE NW Section 4-24S-4W, Reno County, Kansas

Owner: Sterling Drilling Company, et al
Rotary Drilling Contractor: Group Exploration Company

Commenced: June 30, 1967
Completed: July 7, 1967

Rotary Total Depth: 3339'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 220 Sand & Gravel	Run 12 joints 8-5/8" (556.49') set at 569' with 350 sacks SUN SET cement. Plug was down at 10:45 p.m..
220 - 570 Clay, Shale & Sand	
570 - 700 Anhydrite & Shale	
700 - 1005 Shale, Sand & Lime	
1005 - 2225 Lime & Shale	
2225 - 2360 Lime	
2360 - 2690 Shale & Lime	
2690 - 3070 Lime	
3070 - 3299 Shale & Lime	
3299 - 3339 Mississippi Lime T.D.	Run 102 joints 4-1/2" casing (3329.05) threads off. 3040.08' 4-1/2" #J55 8 RN. SS (B condition) 288.98' 9-1/2" #J-55 8 RN. SS (A condition) Set at 3335' with 75 sacks common cement. Job completed at 10:20 p.m..

RECEIVED
STATE CORPORATION COMMISSION

OCT - 3 1979

CONSERVATION DIVISION
Wichita, Kansas