

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Welch

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-B

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 4 TWP. 24S RGE. 4 W

COUNTY Reno

LEASE OPERATOR Producers Oil Company

ADDRESS 427 S. Boston Ste. 711 Tulsa, Ok 74103

PHONE: (918) 582-1188 OPERATORS LICENSE NO. 5232

Date Well Completed 1-28-38

Character of Well Oil

Plugging Commenced 12-30-93

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 1-10-94

The plugging proposal was approved on September 1, 1992 (date)

by David P. Williams (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? NO 1-27-94

Producing Formation Miss Chat Depth to Top 3309 Bottom 3375 T.O. 3375

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS Miss Chat CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Miss Chat	Gas, Oil, Water	3309	3375	12 1/2 7	306 3309	0 0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set  
Ran bailer, hit bridge @ 1600ft. Ran tbg. to 3200 ft., spotted 30 sx cement. Pulled tbg., perforated @ 600ft; ran tbg. to 600 ft., spotted 35 sx cement. Pulled tbg to 400ft, circulated cement from 400 ft to surface. Pulled tbg. Ran 1" to 350' outside casing; circulated cement to surface - one week later filled casing to surface w/ redi-mix cement.

Name of Plugging Contractor Sunflower Well Service License No. 30280

Address P.O. Box 341 Canton, KS 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Producers Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Richard N. Knoblock (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Richard N. Knoblock

(Address) 427 S. Boston Ste/ 711 Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 94

Thy W. Pierce  
Notary Public

My Commission Expires: MY COMMISSION EXPIRES 8-7-06

USE ONLY ONE SIDE OF EACH FORM